Location	ACBIN	<sup>Approximate</sup> Ou <sub>antity</sub> ate	Calegon	Frieble	Conolition 3 Vear October 2027 October	Condition at 6 inconth	Moles Moles
Site No. 55 Memorial							
Basement							
Radio Station Mech	Pipe Insulation		TSI	Yes	MNO	1, 6	Material is located above the finished
Radio Station Mech	Pipe Fitting Insulation		TSI	Yes	MNO	1, 6	ceiling.
Radio Station Mech	Duct Skim Coat		TSI	Yes	MNO	1,6	
Band Room	9" Floor Tile	500 sq. ft.	Misc.	MNO	MNO	1, 6	Materials have been covered over with
Women's Dressing Rm	9" Floor Tile	75 Sq. Ft.	Misc	No	Fair	1, 2	Materials need to be waxed.
Theater Storage (013)	Pipe Insulation	4 linear feet	TSI	Yes	Good	1	Materials is located above the ductwork/closet area.
Mechanical 012	Duct Expansion Cloth	6 Linear ft.	Misc	No	Fair	1	Materials were observed to have water staining present, < 1 lf.
Hall and Foyer outside restrooms end entry to ladies room	9" Floor Tile	580 sq. ft	Misc	No	Fair	1,2	Normal wear throughout with dents, scratches present throughout. Water damage by bubbler.
Storage (002)	9" Floor Tile	80 sq. ft	Misc	No	Good	1	Mostly stored items present. School bookstore owns this space and does not have access.
First Floor							
Stage	Fire Curtain	1 Curtain	Misc.	Yes	Good	1	Suspect, test prior to removal.
Stairwell hall	9" Floor tile	300 sq. ft	Misc.	No	MNO	1,6	Materials have been covered over with
Auditorium	9" Floor tile	4,100 sq. ft	Misc.	No	Fair	1	Materials observed to have some chipped, dented floor tiles present. Two floor tiles in front row broken
Second Floor							
North Stairwell and lobby	9" Floor Tile	540 Sq. Ft.	Misc	No	Good	1	
Auditorium Ceiling	Trowel On Surfacing Material	4,800 sq. ft	Surf	Yes	Good	1	
Auditorium Balcony	9" Floor Tile	2,100 sq. ft	Misc	No	Fair	1, 2	Material was observed to have some chipped and missing floor tiles
Auditorium & Balcony Wall	Trowel On Surfacing Material	400 Sq. Ft.	Surf	Yes	Good	1	

Projector Room	Light wire	2 Linear Ft.	Misc	No	Good	1	Materials are assumed to be ACM.
Attic	Duct Expansion Cloth	40 linear feet	Misc.	No	Good	1	Materials are assumed to be ACM.
Site 013 Music & Dance							
Music							
Exterior: West Side Music	Corrugated transite siding	800 sq. ft	Misc	No	Good	1	
Dance							
Exterior: North Side	Corrugated transite siding	1,500 sq. ft	Misc	No	Good	1	
Alumni Hall							
First Floor	F1 T'1	496 G E	M	NT		1 (	
107/108 Office	Floor Tile	486 Sq. Ft.	Misc	No	MNO	1, 6	Material has been covered over with
101/120/119 Business Office	Floor Tile	486 Sq. Ft.	Misc	No	MNO	1, 6	carpeting.
110/111 Human Resources	Floor Tile	405 Sq. Ft.	Misc	No	MNO	1, 6	
Second Floor		Ĩ					
2nd Floor, Hall Closet	Transite floor	10 sq. ft	Misc	No	Good	1	
2nd Floor, A-1 Kitchen	Linoleum	63 Sq. Ft.	Misc	No	MNO	1, 6	Material has been covered over with
2nd Floor, A-1 Bath	Linoleum	20 Sq. Ft.	Misc	No	MNO	1, 6	newer flooring.
All gender bathroom	Linoleum	12 Sq. Ft.	Misc	No	MNO	1, 6	
(previously listed as Men's							
Bathroom)							
Office Storage	Linoleum	16 Sq. Ft.	Misc	No	MNO	1,6	
Third Floor							
Hall, Bath	Linoleum	75 sq. ft	Misc	No	MNO	1, 6	Material has been covered over with
Apt. 4, Bath	Linoleum	75 sq. ft	Misc	No	MNO	1, 6	newer flooring.
Apt. 5, Bath	Linoleum	100 sq. ft	Misc	No	MNO	1, 6	
Hall Closet	Transite floor	5 sq. ft	Misc	No	Good	1, 6	Material has been covered over with
School House							carpeting.
Basement							
Safe	9" Floor Tile	140 sq. ft	Misc	No	Good	1	
Basement Ceiling	Pipe Insulation		TSI	MNO	MNO	1,6	Material is located above the ceiling.
Basement Ceiling	Pipe Fittings		TSI	MNO	MNO	1,6	is to the use of the contrag.
Basement Electrical Room-	9" Floor Tile		Misc	MNO	MNO	1,6	Majority of material removed by AB
17			Misc	MNO	MNO	1,6	in 2008. Remaining material is
						-	present under the electrical switchgea

(20 sq. ft. approx) and is inaccessible.

Third Floor							
Room 312 Closet	9" Floor Tile	20 Sq. Ft.	Misc	No	Good	1	
Registrar's Office Closet	9" Floor Tile	30 Sq. ft	Misc	No	Good	1	
Physical Plant/Maintenan	ce: Site No. 404						
Boiler Room							
Hall entrance to boiler room	Fire Door	1 Door	Misc.	MNO	MNO	1, 6	Material is assumed to be present underneath metal jacket.
<b>Facilities Building</b>							
Facilities Director office	Pipe Fitting Insulation		TSI	MNO	MNO	1,6	Material was not observed and may be
(former reception/key office)	Pipe Insulation		TSI	MNO	MNO	1,6	above the sheetrock ceiling or within
Maintenance and Secretaries offices	Pipe Insulation		TSI	MNO	MNO	1,6	Material was not observed and may be above the sheetrock ceiling or within
Maintenance and Secretaries offices	Pipe Fitting Insulation		TSI	MNO	MNO	1,6	the wall space.
New Chapel: Site 51							
Choir	Flooring Paper	675 sq. ft	Misc	Yes	MNO	1,6	Material is located under the wood
Side Entrance near choir	Flooring Paper	100 sq. ft	Misc	MNO	MNO	1,6	flooring.
Sacristy Hall	Flooring Paper	475 sq. ft	Misc	MNO	MNO	1,6	
Sacristy	Flooring Paper	220 sq. ft	Misc	MNO	MNO	1,6	
Scudder House: Site No. 4	02						
Second Floor							
Bathroom	9" Floor Tile	75 sq. ft	Misc.	No	Good	1	Prior to removal testing is recommended. Limited access to the materials due to stored materials present.
Friedman Center previous	ly listed as Hargate Art Cer	nter: Site No. 11					
Fire proofing coating	Throughout Attic spaces	15,000 sq. ft.	Surfacing	MNO	MNO	1, 6	Some materials were removed during the 2016-2017 renvoatiosn, however remaining materials have been encpasulated over with gypsum board.
Food Services Site 414							
First Floor							
Upper Dining room	Flooring paper	3,500 sq. ft	Misc.	No	MNO	1, 6	Materials is underneath the wood flooring.
Second Floor							0.

Food services storage room	Flooring paper	240 sq. ft	Misc.	No	MNO	1, 6	Materials is underneath the wood flooring/floor tile.
Women's locker room	Flooring paper	160 sq. ft	Misc.	No	MNO	1, 6	Materials is underneath the wood
Men's locker room	Flooring paper	200 sq. ft	Misc.	No	MNO	1, 6	flooring/floor tiles.
Women's room	Flooring paper	80 sq. ft	Misc.	No	MNO	1, 6	
Break room	Flooring paper	225 sq. ft	Misc.	No	MNO	1, 6	
Linen Storage	Flooring paper	225 sq. ft	Misc.	No	MNO	1, 6	Materials is underneath the wood flooring.
Corridor	Flooring paper	100 sq. ft	Misc.	No	MNO	1, 6	Materials is underneath the wood flooring.
Third Floor							
Guest bathroom	Flooring paper	130 sq. ft	Misc.	No	MNO	1, 6	Materials is underneath the wood
Resident bathroom	Flooring paper	60 sq. ft	Misc.	No	MNO	1, 6	flooring.
Corridor	Flooring paper	360 sq. ft	Misc.	No	MNO	1, 6	
Fourth Floor							
Room 16	Flooring paper	120 sq. ft	Misc.	No	MNO	1, 6	Materials is underneath the wood
Room 17	Flooring paper	160 sq. ft	Misc.	No	MNO	1, 6	flooring.
Room 18	Flooring paper	160 sq. ft	Misc.	No	MNO	1, 6	
Room 19	Flooring paper	160 sq. ft	Misc.	No	MNO	1, 6	
Linen Storage	Flooring paper	50 sq. ft	Misc.	No	MNO	1, 6	
Room 20	Flooring paper	140 sq. ft	Misc.	No	MNO	1, 6	Material is underneath the wood
Room 21	Flooring paper	200 sq. ft	Misc.	No	MNO	1, 6	flooring.
Corridor	Flooring paper	300 sq. ft	Misc.	No	MNO	1, 6	
Post Office: Site No. 406							
First Floor							
Post Master Area	9" Floor Tile and associated mastic	690 sq. ft	Misc.	No	Good	1, 6	Materials have been covered over with new flooring.
Post Master Area	Trowelled-On Surfacing Material	1,477 sq. ft	Misc.	Yes	Good	1	
Red Barn							
First Floor							
Shop	Transite Ceiling Panel	600 sq. ft	Misc.	No	MNO	1, 6	Materials have been enclosed with spray foam insulation.

**Basement Level** 

Boiler Room	Transite Ceiling and Wall Panels	500 sq. ft	Misc.	No	Fair/Damaged	1, 2	Rough edges should be covered or encapsulated. Some areas of broken transite present on walls and ceilings. Area should be priotized for removal.
Nash							
First Floor							
Student room 10	9" Floor tile and mastic	216 sq. ft	Misc.	No	MNO	1, 6	Covered over with carpet.
Student room 11	9" Floor tile and mastic	230 sq. ft	Misc.	No	MNO	1, 6	Covered over with carpet.
Student room 12	9" Floor tile and mastic	230 sq. ft	Misc.	No	MNO	1, 6	Covered over with carpet.
Student room 13	9" Floor tile and mastic	230 sq. ft	Misc.	No	MNO	1,6	Covered over with carpet.
Student room 14	9" Floor tile and mastic	230 sq. ft	Misc.	No	MNO	1,6	Covered over with carpet.
Student room 15	9" Floor tile and mastic	230 sq. ft	Misc.	No	MNO	1,6	Covered over with carpet.
Student room 16	9" Floor tile and mastic	216 sq. ft	Misc.	No	MNO	1,6	Covered over with carpet.
First floor cooridor	9" Floor tile and mastic	128 sq. ft	Misc.	No	MNO	1,6	Covered over with carpet.
Second Floor							
Student room 20	9" Floor tile and mastic	170 sq. ft	Misc.	No	MNO	1, 6	Covered over with carpet.
Student room 21	9" Floor tile and mastic	121 sq. ft	Misc.	No	MNO	1, 6	Covered over with carpet.
Student room 22	9" Floor tile and mastic	121 sq. ft	Misc.	No	MNO	1, 6	Covered over with carpet.
Student room 23	9" Floor tile and mastic	121 sq. ft	Misc.	No	MNO	1, 6	Covered over with carpet.
Student room 24	9" Floor tile and mastic	121 sq. ft	Misc.	No	MNO	1, 6	Covered over with carpet.
Student room 25	9" Floor tile and mastic	121 sq. ft	Misc.	No	MNO	1, 6	Covered over with carpet.
Student room 26	9" Floor tile and mastic	170 sq. ft	Misc.	No	MNO	1, 6	Covered over with carpet.
Student room 27	9" Floor tile and mastic	216 sq. ft	Misc.	No	MNO	1, 6	Covered over with carpet.
Corridor	9" Floor tile and mastic	500 sq. ft	Misc.	No	MNO	1, 6	Covered over with carpet.
Throughout	Other suspect ACBM is pre-	sent in and on t	he building th	at requires furth	ner review, testing, asses	sement and,	See further discussion in report.

based on the results modifications to the management plan may be required. In addition, interior and exterior Possible inaccessible ACBM also.